Estimates in hand as below. (Note: some of these are likely out-of-date and need revision):

- D'Avanza Clock Repair (12/14/16)
- Vanguard Scaffolding (5/10/19)

D'Avanza Clock Repair LLC

Tower Clock Repair and Restoration

Proposal
12/14/2016

Meeting House Clock Face Repair

Scope of Work

Restore clock faces on meetinghouse clock tower Paint clock faces. Re-gild numerals, minute and hour marks. Make new hands to match original and gild with 23K gold leaf. All work to conform to the Secretary of the Interior's Standards for Rehabilitation.

Work to be Performed

1- Remove hands, numerals, minute and hour marks
2- Prep, prime and paint clock faces with Sherwin Williams Duration
3- Fabricate new clock hands from clear heart vertical grain Western red cedar
4- Hands to match original in design and profile
5- Hands to be tapered lengthwise and mounted to their hubs with copper rivets
6- Balance hands and paint tails black
7- Prime, prep and gild hands with 23K gold leaf
8- Prep and gild numerals, minute and hour marks with 23K gold leaf
9- Secure components with brass screws
10- Install hands, synchronize dials and set to correct time

Cost: $12,925.00

1/3 Deposit
Balance net 15 days

440 East Dunbarton Road • Goffstown, NH 03045 • 603-497-2256 • FAX 603-497-3160
phil@davanzaclocks.com • www.davanzaclocks.com

Scaffolding to very top of Tower:

Vanguard Scaffolding
P.O. Box 247
New Ipswich, NH 03071
Ph: 800 624-5000
-3273

Vanguard

HYDRO MOBILE

Customer: **Town of Jaffrey** Date: 5/10/19

Project: Meetinghouse Steeple Repair

Prepared by: Dutch

Phase	Description	Labor Charge
0	Installation and dismantle of frame scaffold for repair work on steeple.	$ -
0	Scaffold to have 2 full plank decks. The first deck will be at the base	$ -
0	of the clock and the second will be at the railing above the bell. A	$ -
0	stair access will be provided for acccess to work areas. Scaffold	$ -
0	will meet all OSHA regs. Plywood will be placed on top of sills to	$ -
0	protect the new roof. An alternate price will include all scaffold from	$ -
0	bell tower deck up the remainder of steeple to the weathervane.	
0	Price does not include any engineering or drawings. All scaffold	$ -
0	installed by trained and certified scaffold erectors.	$ -
0	Rental/28 day	$ 3,200.00
0	Installation	$ 13,500.00
0	Dismantle	$ 6,750.00
0		

Terms & Notes

Sub total	$ 23,450.00
Tax	
Delivery	$ 400.00
Pick Up	$ 400.00
Total	**$ 24,250.00**

All quoted prices are subject to applicable sales tax

Accepted by: _____

Date: _____

Alternate: Scaffolding upper portion of Tower only:

Vanguard Scaffolding
P.O. Box 247
New Ipswich, NH 03071
Ph: 800 624-5000
-3273

HYDRO MOBILE

Customer: **Town of Jaffrey** Date: 5/10/19

Project: Meetinghouse Steeple Repair
Alternate price

Prepared by: Dutch

Phase	*Description*	*Labor Charge*
0	Installation and dismantle of frame scaffold for repair work on steeple.	$ -
0	from the bell section railing to the top. This includes 100% sidearm	$ -
0	levels and stair access to top of weathervane.	$ -
0		$ -
0		$ -
0		$ -
0		
0		$ -
0		$ -
0	Rental/28 day	$ 1,500.00
0	Installation	$ 6,750.00
0	Dismantle	$ 3,375.00
0		

Terms & Notes

Sub total	$ 11,625.00
Tax	
Delivery	$ 200.00
Pick Up	$ 200.00
Total	**$ 12,025.00**

All quoted prices are subject to applicable sales tax

Accepted by: _____

Date: _____